

जाहीर निविदा सूचना

सेक्रेटरी, श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, चंदगड जिल्हा कोल्हापूर यांचेकडून नोंदणीकृत अभियंता/मत्तेदार यांना काळविणेत येते की, चंदगड येथील श्री. महालक्ष्मी मंदिर बांधकाम करणे कामाची निविदा दोन लिफाफा पद्धतीने निविदा मागवीत आहे. सदर निविदा श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, (<http://www.shridevravalnath.co.in/itihas.html>) या संकेत स्थळ व श्री देव रवळनाथ ट्रस्ट कार्यालय मध्ये दि. २३/०८/२०२५ रोजी सकाळी. ११.०० वाजलेपासून ते दि. ०३/०९/२०२५ रोजी ०१.०० वाजेपर्यंत पहावयास मिळतील. १) निविदेचा कोरा नमूना फॉर्म दिनांक २३/०८/२०२५ सकाळी ११.०० ते दिनांक ०३/०९/२०२५ रोजी दुपारी ०१.०० वाजेपर्यंत शासकीय सुट्टीचे दिवस वगळून रोखीने विकत मिळतील. २) विहित पद्धतीने दर नमूद केलेली दरपत्रके श्री देव रवळनाथ ट्रस्ट कार्यालयामध्ये दिनांक २३/०८/२०२५ सकाळी ११.०० ते दिनांक ०३/०९/२०२५ दुपारी ०१.०० वाजेपर्यंत सीलबंद निविदा दाखल करणेत यावेत. ३) ऑफलाईन पद्धतीने सादर केलेल्या निविदा दिनांक ०४/०९/२०२५ रोजी दुपारी १.०० वाजता यांचे श्री देव रवळनाथ ट्रस्ट कार्यालयात उपस्थित मत्तेदार अथवा त्यांनी प्राधिकृत केलेल्या प्रतिनिधीचे उपस्थितीत उघडणेत येतील.

टीप :- इतर अटी व शर्ती त्याची अंदाजपत्रके श्री देव रवळनाथ ट्रस्ट कार्यालयात कार्यालयीन वेळेत पाहणेस मिळतील.

दिनांक :- २२/०३/२०२५

सही/-

(श्री सुरेश सातवनेकर)

सेक्रेटरी

श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, चंदगड

श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, चंदगड

जाहीर निविदा सूचना

सेक्रेटरी, श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, चंदगड जिल्हा कोल्हापूर यांचेकडून नोंदणीकृत अभियंता/मत्तेदार यांना काळविणेत येते की, चंदगड येथील श्री. महालक्ष्मी मंदिर बांधकाम करणे कामाची निविदा दोन लिफाफा पद्धतीने निविदा मागवीत आहे. सदर निविदा श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, (<http://www.shridevravalnath.co.in/itihas.html>) या संकेत स्थळ व श्री देव रवळनाथ ट्रस्ट कार्यालय मध्ये दि. २३/०८/२०२५ रोजी सकाळी. ११.०० वाजलेपासून ते दि. ०३/०९/२०२५ रोजी ०१.०० वाजेपर्यंत पहावयास मिळतील.

अ.क्र	कामाचे नाव	अंदाजित रक्कम रुपये	टेंडर बयाणा रक्कम 1%	सुरक्षा ठेव 2%	काम पूर्ण करणेची मुदत	कोरी निविदा रक्कम रु.
1	2	3	4	5	6	7
1	चंदगड येथील श्री. महालक्ष्मी मंदिर बांधकाम करणे.	र.रु ९,१४,९८२/-	र.रु ९१५०/-	र.रु १८३००/-	३०० दिवस	५००

- १) ई-निविदेचा कोरा नमुना संच <http://mahatenders.gov.in> या दि. २३/०८/२०२५ रोजी सकाळी. ११.०० वाजलेपासून ते दि. ०३/०९/२०२५ रोजी ०१.०० वाजेपर्यंत ऑनलाईन पहावयास मिळतील व Download करता येतील.
- २) उपरोक्त सर्व कामाबाबत निविदा अटी व शर्ती इ.बाबतचा तपशिल निविदा संचामध्ये नमूद केला आहे. परिपूर्णरित्या भरलेल्या ई-निविदा या दि. २३/०८/२०२५ रोजी सकाळी. ११.०० वाजलेपासून ते दि. ०३/०९/२०२५ रोजी ०१.०० वाजेपर्यंत स्विकारण्यात येतील.
- ३) उपरोक्त तक्त्यातील कामाचे नावासमोर रकाना क्रं. ४ व क्रं. ७ मध्ये नमूद रक्कम <http://mahatenders.gov.in> या संकेतस्थळावरून Online पद्धतीने भरणेची आहे.
- ४) निविदेच्या अटी शर्तीमध्ये बदल करणे प्राप्त निविदापैकी एक किंवा सर्व निविदा कोणतेही कारण न देता नाकरणेचा हक्क नगरपरिषदेने राखून ठेवला आहे.
- ५) ऑनलाईन पद्धतीने सादर केलेल्या निविदा दिनांक ०४/०९/२०२५ रोजी ०१.०० श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, चंदगड जिल्हा कोल्हापूर यांचे कार्यालयात उपस्थित मत्तेदार अथवा त्यांनी प्राधिकृत केलेल्या प्रतिनिधींचे उपस्थितीत उघडणेत येतील.

सही/-

(श्री सुरेश सातवनेकर)

सेक्रेटरी

श्री देव रवळनाथ देवस्थान पब्लिक ट्रस्ट, चंदगड

NAME OF WORK :- Details estimation for the proposed construction of a **PShri Mahalaxmi Temple** in T P No. at Kumbar Galli Chandagad, Taluka- Chandagad, Dist- Kolhapur.
For :- .

ABSTRACT SHEET


Date - 08-08-2025

Sl. No.	Description	Qty	Units	Rate	Amount
1	Excavation for foundation including disposing off the excavated stuff as directed up to a lead of 100' & lift of 6' in soil and murum.	10.00	Cum	550.00	5500.00
2	Providing boulder soling including filling the crevices with chips of sand or murum and ramming, watering etc. complete.	6.00	"	1400.00	8400.00
3	Providing murum filling including filling the crevices with chips of sand or murum and ramming, watering etc. complete.	15.00	"	550.00	8250.00
4	Providing Cement concrete 1:4:8 for Bed using graded aggregates 1" to 1 1/2" metal including ramming, curing, etc. complete.	3.50	"	5300.00	18550.00
5	Providing C.C. 1:1,1/2 :3 (M-20) for R.C.C. column footings using graded aggregates 2.54 cm and below including centering, compaction, finishing, curing, etc. complete.	3.60	"	12350.00	44460.00
6	Providing C.C. 1:11/2:3 (M-20) for R.C.C. column using graded aggregates 2.54 cm and below including centering, compaction, finishing, curing, etc. complete.	7.50	Cum	15550.00	116625.00
7	Providing C. C. 1:11/2:3 (M-20) for plinth level beams using graded aggregates 2.54 cm and below including centering, compaction, finishing, curing etc. complete.	2.50	"	15550.00	38875.00
8	Providing and constructing 15"th black stone masonry in C.M. 1:6 for super structure including scaffolding, curing, etc. complete deducting for doors and window and openings.	12.00	Cum	10600.00	127200.00
9	Providing and constructing 4.1/2"th brick masonry for partition wall in C.M. 1:4 including curing etc. deducting for doors and window and openings.	12.00	Sqm	1300.00	15600.00
10	Providing c.c 1:2:4 for Lintel using graded aggregates 2.54 cm. And below including form work, compaction, finishing, curing etc,	2.40	Cum	15550.00	37320.00
11	Providing c.c 1:11/2:3 (M-20) for Slab using graded aggregates 2.54 cm. And below including centering compaction, finishing, curing etc,	3.20	Cum	15550.00	49760.00

12	Providing c.c 1:11/2:3 (M-20) for Slab level Beam using graded aggregates 2.54 cm. And below including centering compaction, finishing,	1.80	Cum	15550.00	27990.00
13	Providing c.c 1;2:4 for chajja fins, design drops , using graded aggregates including 1:9 c.m and below including centering reinforcements at compaction finishing all exposed surfaced with cement plaster in c.m. 1:4 and red ochre finishing for shelves and racks,	7.00	Sqm	3000.00	21000.00
14	Providing and fixing Teak wood frame 5"X5" for doors with Teak wood paneled shutters including necessary fixture and fastening such as iron oxidized hinges and aluminums fixtures etc. complete.	3.50	Sqm	16200.00	56700.00
15	Providing and fixing aluminums Windows with aluminums paneled shutters including necessary fixture and fastening such as iron oxidized hinges and aluminums fixtures etc. complete.	3.25	Sqm	4850.00	15762.50
16	Providing cement plaster single coat in C. M. 1:6 inner surfaces of walls including smooth neeru finishing and curing etc. complete.	40.00	Sqm	480.00	19200.00
	a) Ground floor	150.00	Sqm	270.00	40500.00
	b) First floor	150.00	"	270.00	40500.00
17	Providing sand faced double coat cement plaster in C.M. 1:4 for external surfaces of walls including curing, etc. complete.				0.00
18	Proving fixing provided quality Vitrified tiles for flooring set in cement over back coat including finishing, curing, etc, complete.	40.00	Sqm	1600.00	64000.00
19	Providing fixing provided Granite tiles for dadoing set in cement over back coat including finishing, curing, etc, complete.	12.00	Sqm	3000.00	36000.00
20	Total Amount =				792192.50
21	10% add extra for plumbing, painting, & electrification works.				79219.25
22	Total Amount =				871411.75
23	5% add extra for Architect consulting charges.				43570.59
24	Total Amount				914982.34

Say

914982.00



H. L. KUGAJI
Consulting Civil Engineer
Annapurna Krupa Apartment,
3rd Floor, Near Goaves Circle,
Khanapur Road, Tilakwadi,
Belgaum - 590006
Cell : 9448148476